

NABARD

राष्ट्रीय बैंक स्टाफ

महाविद्यालय

NBSC

**National Bank Staff
College**

ISO 9001:2000 Certified Institution

प्ल डी ए कालोनी

कानपुर रोड

लखनऊ -226012

दूरभाष : [O] 0522-

2421044/62/65 फैक्स :

0522-2421035

website : www.nbsc.in

सेक्टर-एचSector-H

LDA Colony

Kanpur Road

Lucknow-226012

Phone : [O] 0522-2421044/62/65

Fax : 0522-2421035

e- mail : nbsc@sancharnet.in

मानस की उत्कृष्टता हमारा ध्येय - SHAPING MINDS TO EXCEL

रा.बैं. स्टाफ महा. लख./ / PR-21 / Rain Water Harvesting /2010-11

दिनांक 07 March 2011

मैसर्स

.....

.....

प्रिय महोदय

राष्ट्रीय बैंक स्टाफ महाविद्यालय – Providing Rain Water Harvesting structures & associated works at NBSC, Lucknow

1. इस दस्तावेज में दिए गए विवरण के अनुसार आप राष्ट्रीय बैंक स्टाफ महाविद्यालय के लिए उक्त कार्य करने के लिए टेंडर हेतु आमंत्रित हैं.
2. पूरे कार्य की अनुमानित लागत रूपए 1,75,000/- (रूपए एक लाख पचहत्तर हजार मात्र) हैं व इसे कार्य आदेश की तिथि के 15 दिन के के भीतर पूरा किया जाना है.
3. टेंडर दस्तावेज जिसमें कॉन्ट्रैक्ट की शर्त, विशेषताएं, मात्राओं की सारणी शामिल है, को प्रधानाचार्य, राष्ट्रीय बैंक स्टाफ महाविद्यालय, सेक्टर एच, एलडीए कालोनी, कानपुर रोड, लखनऊ - 226012 से **दिनांक 07 March 2011 से 14 March 2011** के दौरान किसी भी कार्य दिवस (सोमवार से शुक्रवार) पर रूपए 150/- (रूपए एक सौ पचास मात्र) की राशि, जो वापस नहीं की जाएगी, के भुगतान पर प्राप्त किया जा सकता है अथवा इसे हमारी बैवसाइट www.nabard.org/tenders or www.nbsc.in से डाउनलोड किया जा सकता है. जो फर्म आवेदन फार्म व कार्य से संबंधित अन्य दस्तावेज हमारी बैवसाइट से डाउनलोड करते हैं, उन्हें उक्त कार्य के लिए आवेदन फार्म व टेंडर दस्तावेज प्रस्तुत करते समय रूपए 150/- (रूपए एक सौ पचास मात्र) की राशि, जो वापस नहीं की जाएगी, डिमाण्ड ड्रॉफ्ट के माध्यम से हमारे कार्यालय में जमा करनी होगी.

4. पूरी तरह से भरे हुए व श्री श्री आर अमलोरपवनाथन, प्रधानाचार्य, राष्ट्रीय बैंक स्टाफ महाविद्यालय, सेक्टर - एच, एल डी ए कॉलोनी, कानपुर रोड, लखनऊ - 226 012 को संबोधित सीलबन्ध टेंडर प्रधानाचार्य सचिवालय में इस प्रयोजन हेतु रखे गए टेंडर बॉक्स में दिनांक **14 March 2011** को **15.00 बजे तक अथवा उससे पहले** जमा कर दें उन्हें उसी दिन **15.30 बजे** टेंडरकर्ताओं अथवा उनके प्राधिकृत प्रतिनिधियों, जो उपस्थित होंगे, की उपस्थिति में खोला जाएगा.
5. राष्ट्रीय बैंक स्टाफ महाविद्यालय, लखनऊ के पक्ष में देय डिमाण्ड ड्राफ्ट के माध्यम से रुपए **3,500/- (रुपये** तीन हजार पाँच सौ मात्र) बयाने की राशि (Earnest Money Deposit) मुहरबन्द लिफाफे में कोटेशन के साथ जमा करवाई जानी चाहिए. निर्धारित समय तक प्राप्त सभी टेंडर खोले जाएँगे लेकिन बयाने की राशि के बिना प्राप्त टेंडर नामंजूर कर दिए जाएँगे. चेक के माध्यम से बयाने की राशि स्वीकार नहीं की जाएगी. सफल टेंडरकर्ता की बयाने की राशि जमानत जमा / प्रतिधारण राशि (retention money) के रूप में रख ली जाएगी. इस राशि पर कोई ब्याज देय नहीं होगा.
6. उपर्युक्त समय व तिथि के पश्चात् प्राप्त टेंडर नामंजूर किए जा सकते हैं.
7. राष्ट्रीय बैंक स्टाफ महाविद्यालय न्यूनतम अथवा अन्य कोई टेंडर स्वीकार करने को बाध्य नहीं है तथा प्राप्त हुए किसी भी अथवा सभी टेंडरों को बिना कोई कारण बताए नामंजूर करने, उन पर मोलभाव करने तथा काम को बाँटने का अधिकार उसके पास सुरक्षित रहेगा.
8. मूल्य बोली (price bid) खोले जाने की तिथि से न्यूनतम 90 (नब्बे)दिन के लिए टेंडर वैध रहेगा.
9. जो टेंडर उपर्युक्त शर्तों में से किसी या सभी शर्तों को पूरा नहीं करते अथवा जो किसी भी दृष्टि से अपूर्ण हैं, नामंजूर किए जा सकते हैं.
10. मूल्य बोली में दरें अंकों व शब्दों दोनों में दी जानी चाहिए तथा इन दोनों में कोई विसंगति होने की स्थिति में शब्दों में लिखी गई राशि मान्य होगी.
11. टेंडरर अथवा उसके प्राधिकृत प्रतिनिधि द्वारा टेंडर दस्तावेज के प्रत्येक पृष्ठ पर विधिवत हस्ताक्षर किए जाने चाहिए. किसी भी प्रकार के अधिलेखन (overwriting), सुधार अथवा रद्दीकरण को मुहर के साथ विधिवत रूप से प्राधिकृत किया जाना चाहिए. टेंडर दस्तावेज के साथ दस्तावेज के हस्तक्षारकर्ता के पक्ष में संपूर्ण पॉवर ऑफ एटोर्नी की सत्यापित प्रति होनी चाहिए.
12. कॉन्ट्रक्ट दस्तावेज में कोई विसंगति, चूक, अनिश्चितता अथवा विरोध अथवा इसके अर्थ को लेकर किसी शंका को राष्ट्रीय बैंक की नोटिस में लाया जाए. बैंक इनकी समीक्षा करेगा व जहा चाही गई जानकारी के

बारे में स्पष्ट रूप से निर्दिष्ट नहीं किया गया है, सभी टेंडरर को एक स्पष्टीकरण जारी कर देगा जो कॉन्ट्रैक्ट दस्तावेज का भाग होगा. बैंक किसी भी मौखिक सूचना के लिए जिम्मेदार नहीं होगा.

13. बैंक द्वारा टेंडरकर्ता को टेण्डर मंजूर हो जाने की सूचना जारी होते ही यह करार टेण्डरकर्ता (tenderer) पर बाध्यकारी (binding) हो जाएगा.

भवदीय

(मुकेश वत्स)

सहायक महाप्रबंधक

Encl. : 1) General terms & conditions

2) Schedule of Quantity

3) Drawing

General Terms and conditions for Providing Rain Water Harvesting structures & associated works at NBSC, Lucknow

1. The defects liability period shall be one year from the date of virtual completion.
2. The RMD@5% shall be deducted from the bill of contractor which will be released after completion of defects liability period.
3. Tax deduction at source (Income Tax & Works Contract Tax) as per rules would be deducted from the payments.
4. The contractor will follow all the applicable labour laws.
5. The contractor will take insurance cover for all the skilled/unskilled persons employed by him.
6. The quoted rates shall be inclusive of carting away debris to nearest municipal dump & cleaning the floors ,doors, windows, glasses etc.
7. The agency will take care while carrying out excavation & boring for the works. Due precaution should be taken at the time of excavation and it should be ensured that the underground power cables, waterpipelines etc. are not damaged.
8. The work shall be done with utmost precaution and without causing any damages to Bank's property/equipment/installations. Damages done, if any, would be recovered from the contractor.
9. The EMD of **Rs.3,500/-** shall be deposited by demand draft payable to **National Bank Staff College**.
10. All materials shall be got approved from Bank before start of work.
11. Measurements shall be taken according to IS:1200 unless otherwise specified.
12. Any extra item required for proper completion of work shall be got approved from the Bank & shall be paid on actual cost of labour & materials plus 15% towards overheads & profit.
13. The dispute, if any, shall be resolved as per Arbitration & Reconciliation Act.
14. No payment shall be made for defective work.
15. The contractor will submit bill with measurement sheets, wherever applicable. No bills, without measurements shall be accepted.
16. The quoted rates shall remain valid for 90 days for acceptance.
17. The quantities in the SOQ are indicative & can increase or decrease during execution of work, no claim on this account shall be admissible.
18. The contractor will quote rates according to SOQ, incomplete or partly filled tenders shall be rejected.
19. The total time allowed for completing the work is **15 days** from the date of issue of work order. Contractor may carry out work in shifts excluding night. There will be no extension of time on any account.
20. The bank reserves the right to reject any or all the bids without assigning any reason.

Date :

Place :

Signature of agency with seal

APPENDIX

SCHEDULE OF FISCAL ASPECTS

| S No | Item | Details |
|------|--|---|
| 1 | Earnest Money Deposit | Rs. 3,500/- (Rupees Three Thousand Five Hundred Only) to be deposited with tender |
| 2 | Possession of site | Immediately on award of work |
| 3 | Time of completion | Within 15 days from the date of the site is handed over or from the day of date of issue of work order, whichever is later |
| 4 | Payment of final bill | Within one month from the date of receipt of bill |
| 5 | Retention money/security deposit bills | 05 (Five) percent of value of work shown in bills |
| 6 | Release of retention money | The retention amount shall be refunded after one year from the date of virtual completion, subject to satisfactory rectification of defects, if any |
| 7 | Defects liability period | 12 (Twelve) months from the date of virtual completion |

EMPLOYER

CONTRACTOR

NATIONAL BANK STAFF COLLEGE

SCHEDULE OF QUANTITIES

Preamble :

The rates quoted shall include the following :

- i. The contractor will keep record of material brought to site and get it inspected before use.
- ii. The bank may allow the representative of manufacturer to inspect the materials.
- iii. The work shall be carried out as per manufacturers specifications.
- iv. The work shall be carried out both during/after working hours and even on holidays if situation so warrants.
- v. The successful tenderers will be required to prepare a sample of an item for approval by the Bank and if required, carry out any changes as per Banks advise without any extra cost to the Bank.

Schedule of Quantities
Providing Rain Water Harvesting structures & associated works at NBSC, Lucknow

| Sl. No. | Item description | Qty. | Unit | Rate (Rs.) | Amount (Rs) |
|---------|---|------|--------|------------|-------------|
| 1 | Earth work in excavation by mechanical means/manual means including disposal of excavated earth, lead upto 50m and lift upto 2.5m, disposed earth to be levelled and neatly dressed.(All kinds of soil) | 70 | Cu.Mtr | | |
| 2 | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m. | 50 | Cu.Mtr | | |
| 3 | Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: Cement Mortor 1:4 (1cement :4 Coarse sand) | 08 | Cu.Mtr | | |
| 4 | 12 mm cement plaster of mix : 1:4 (1 cement : 4 coarse sand) | 34 | Sq Mtr | | |
| 5 | Providing and fixing P.V.C waste pipes : (6kg /cm ² working pressure ISI Marked with including all fittings, fixtures specials. jointing of pipes (Tirupati, Ganga, Finolex, Supreme make) including floor cutting & making good with cement concrete. | | | | |
| 5.1 | 150 mm dia | 04 | Mtr | | |
| 5.2 | 100 mm dia | 120 | Mtr | | |
| 6 | Providing and fixing slotted P.V.C , waste pipes : (6kg /cm ² working pressure) ISI Marked with including all fittings, fixtures specials. jointing of pipes for fixing in boring (Tirupati, Ganga, Finolex, Supreme make) 150 mm dia | 30 | Mtr | | |
| 7 | Supplying and packing of stone boulder of size 10to 20cm in filtration chamber as per direction of Engineer in charge. | 24 | Cu.Mtr | | |
| 8 | Supply and packing with pea gravel of 1.5 to 4.8mm nominal size in trenches | 9 | Cu.Mtr | | |
| 9 | Supply and packing with pea gravel of 1.5 to 4.8mm nominal size around P.V.C pipes for packing around boring | 01 | Cu.Mtr | | |

| Sl. No. | Item description | Qty. | Unit | Rate (Rs.) | Amount (Rs) |
|---------|---|------|--------|------------|-------------|
| 10 | Supplying and filling of fine sand as per direction of Engineer in charge. | 02 | Cu.Mtr | | |
| 11 | Supplying and filling of coarse sand (mooram) as per direction of Engineer in charge. | 09 | Cu.Mtr | | |
| 12 | Boring/Drilling i/c reaming if necessary bore hole in all kind of soil excluding rock complete.250mm dia the bore hole from ground level to be 9 to 13 m depth. | 02 | Job | | |
| 13 | Development of tube well: (a) By air compressor of heavy duty. | 02 | Job | | |
| | TOTAL | | | | |

TOTAL Amount in Words :

DATE:

SIGNATURE OF TENDERER WITH SEAL

PLACE:

NOTE : TENDERER SHOULD QUOTE RATES & AMOUNT BOTH IN WORDS & FIGURE