

रा.बैं.उ.प्र.क्षे.का./जी.ए.डी.-परिसर/  
22 जून 2007

/पीडी एम /2007-08

प्रिय महोदय,

**गोमती नगर स्थित कार्यालय परिसर में कोरिडोर में मैट बिछाने का कार्य**

राष्ट्रीय बैंक उक्त कार्य हेतु अनुमोदित ठेकेदारों/आपूर्तिकर्ताओं से निविदाएं आमंत्रित करता है। कार्य का विवरण संलग्न है:-

1. कार्य का नाम : मैट की आपूर्ति एवं बिछाने के कार्य हेतु
2. कार्य स्थल : 11, विपिन खण्ड गोमती नगर, लखनऊ
3. धरोहर राशि : रु 2000.00
4. निविदा जमा करने की अन्तिम तिथि : 9 जुलाई 2007 सायंकाल 15:00 बजे तक
5. निविदा खोलने की तिथि : 9 जुलाई 2007 सायंकाल 15:30 बजे

कृपया निविदा भरने से पूर्व कार्यस्थल में किए जाने वाले कार्य का निरीक्षण कर लें । निविदा प्रपत्र कार्यालय समय में निशुल्क जारी किए जाएंगे । निविदा प्रपत्र राष्ट्रीय बैंक की वेबसाइट [www.nabard.org](http://www.nabard.org) पर भी उपलब्ध हैं इच्छुक एजेंसियां डाउनलोड कर सकती हैं । मुहरबन्द निविदाएं, जो कि श्री सुखबीर सिंह, मुख्य महाप्रबन्धक को सम्बोधित हो निर्धारित समय तक राष्ट्रीय बैंक क्षेत्रीय कार्यालय में द्वितीय तल पर जीएडी विभाग में रखे गए टेण्डर बाक्स में डालना होगा । देर से प्राप्त या अधूरी निविदाओं पर विचार नहीं किया जाएगा । बैंक किसी एक या सभी निविदाओं को बिना कारण बताए अस्वीकार करने का अधिकार सुरक्षित रखता है ।

भ व दी य

( मुकेश वत्स )  
सहायक महाप्रबन्धक

**Quotation for supply and fixing of mat for office building**

S.No.	Description	Quantity	Rate	Amount
1	Supply and laying of loop pile mat in 1.22m width (4 ft) in corridor of office building meeting following specification. Pile Fibre - 100% BCF polypropylene Yarn construction :Bulk continuous filament Yarn type : Solution dyed Pile weight : 450 gms/m <sup>2</sup> Pile height : 5mm (±) 5% Primary backing : 90 gms/m <sup>2</sup> Secondary backing : 55 gms/m <sup>2</sup> Warranty : 5 year  Make : Unitex (Flute) or equivalent approved.	170 Sq.m		

Total:

Signature of the contractor

Place :

Date :

### **Terms & conditions for supply of mat**

1. The defects liability period shall be one year from date of completion.
2. The RMD@5% shall be deducted from the bill of contractor which will be released after completion of defects liability period.
3. The I .Tax & WCT shall be deducted as per current rules.
4. The contractor will follow all the labour laws applicable from time to time.
5. The quoted rates shall be inclusive of carting away debris to nearest municipal dump & cleaning the floors ,doors, windows, glasses etc.
6. The EMD of Rs.2000/- shall be deposited by demand draft payable to NABARD.
7. All material shall be got approved from bank before start of work.
8. Measurements shall be taken according to IS:1200 unless otherwise specified.
9. The dispute, if any, shall be resolved as per Arbitration & Reconciliation Act.
10. No payment shall be made for defective work.
11. The contractor will submit bill with measurement sheets. No bills ,without measurements shall be accepted.
12. The quoted rates shall remain valid for 90 days for acceptance.
13. Bank reserves the right to accept or reject any tender .
14. Liquidated damages @ of Rs.NIL / week of delay will be deducted from contractor's bill if the work is not completed in time( including authorised extensions). The contractor will request for time extension well in time if there are any hindrances in completion of work which are beyond control.
15. Contractor should take actual measurement at site before placing order to manufacturer.

Place:

Date:

Signature of contractor  
with seal & address