

NABARD EXECUTIVE VISITING OFFICERS FLAT (NO. 84) AT EXHIBITION ROAD, PATNA

SCHEDULE OF QUANTITIES (S.O.Q.)					
Sl. No.	Description Of Work	Unit	Qty	Rate	Amount(Rs.)
A	DISMANTLING WORK				
1	Dismantling brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	CUM	8.45		
2	Dismantling R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	CUM	0.24		
3	Dismantling tile work in floors and wall laid in cement mortar including stacking material within 50 metres lead. 15.23.1 For thickness of tiles 10mm to 25mm	SQM	79.39		
4	Carriage for removal of debris by tractor/ tipper	NOS.	2.00		
5	Dismantling doors, windows and celestory windows (steel or wood) shutter including, chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead: 15.11.1 of area 3 sq. Metres and below	NOS.	2.00		
6	Dismantling electrical wires manually/by mechanical means including stacking of materials 50 metres lead as per direction of Engineer-In-Charge.	LS	3.00		
	SUB TOTAL (DISNAMTLING WORK)				
B	PAINTING WORKS				
1	Providing and Applying Premium Plastic Emulsion paint on wall of any desired colour of two or more coats approved brand and manufacture to give an even shade, with one coat of primer and 2 coats of wall putty with roller finish as recommended by the Manufacturer, specified in the drawings & directed by the engineer in charge.				
a	For internal wall	sqm	200.00		
b	Texture painting as per architect's instruction	sqm	40.00		
	SUB TOTAL (PAINTING WORK)				

C	FLOORING & CLADDING WORKS				
1	Providing and laying vitrified floor tiles- Italian Shade Double charged in size (800x800 mm} thickness to be specified by the manufacture with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colour and shades laid on 20mm thick cement mortal 1:4 (1 cement:4 coarse sand) jointing with grey cement slurry @3.3kg/sqm including skirting, grouting the joints with white cement and matching pigments etc complete in all respect. DSR:11.41.2 Size of tile 800x800 mm	sqm	103.21		
	SUB TOTAL (FLOORING WORK)				
D	WOOD WORK				
1	14.28 Providing and fixing brass curtain rods of wall thickness 1.25 mm with two brass brackets fixed with brass screws and wooden plugs etc. wherever necessary complete. 14.28.1 20 mm diameter. metre 222.10	RMT	6.20		
2	Providing and fixing wall design in ply (water proof 12mm) and laminate (1mm) as per drawing.	sqm	13.00		
3	Reveneering and repairing of all wardrobe and shutter.	sqm	7.81		
4	Providing and fixing shoes rack.	NOS.	1.00		
5	Providing and fixing T.V. cabinet.	NOS.	2.00		
	SUB TOTAL (WOOD WORK)				
E	ELECTRICAL WORK				
1	Wiring for light point/fan point/ exhaust fan point/ call bell point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq mm FRLS PVC insulated copper conductor single core cable etc. as required. 1.10.3 Group C	POINT	12.00		

2	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	METRE	60.00		
3	Supplying and fixing following size/modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
4	3 Module (100mmX75mm)	EACH	20.00		
5	8 Module (125mm X 125mm)	EACH	8.00		
6	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "c" curve including connections ,paiting etc. as required.	EACH	3.00		
7	Supplying and fixing following modular switch/socket on the existing modular plate & switch box inluding connections but excluding modular plate etc. as required.				
a	1.24.3 - 15/16 A switch	EACH	20.00		
b	1.24.5 - 6 pin 15/16 A socket outlet	EACH	8.00		
	SUB TOTAL (ELECTRICAL WORK)				
F	SLIDING FOLDING WINDOW				
1	Providing and fixing sliding folding full height window made with powder coating aluminium Frame with 12mm toughened glass inside. Rate includes all the components involved in installation.	sqm	8.78		
	SUB TOTAL (SLIDING FOLDING WINDOW)				
G	MISCELLANEOUS WORK				
a	Vertical blind in window.	sqm	8.78		
b	Sensor light in both toilet.	NOS.	2.00		
	SUB TOTAL				
	Grand Total				

Amount in words:

Rate should be excluding GST

GST as applicable will be paid extra