National Bank for Agriculture and Rural Development, HP Regional Office, Block No.32, SDA Complex, Kasumpti, Shimla-171009



<u>Tender for providing HDF Laminated Wooden Flooring at NABARD, HP Regional Office, Block No.32, SDA Complex, Kasumpti, Shimla-171009</u>

PART II (Financial Bid)

Section 2
FINANCIAL BID
SCHEDULE OF QUANTITIES

Schedule of Quantities for providing of HDF Laminated wooden flooring at NABARD Office, Block 32, SDA Complex, Kasumpati, Shimla - 171009

Item No.	Description of work	Approx . Qty	Unit	Rate (Rs)	Total Amount (Rs.)
1	Providing and fixing of HDF (High density Fiber Board) Laminated Wooden Flooring measuring 1214mm X 193mm +/- 5% and thickness of 12mm +/- 5% of "Action Tesa", "Kaara" make or equivalent brand and of approved shade with HDF floor in the NABARD Office by removing already installed old carpets etc. and levelling of floor wherever required, filling up the holes on the floor with cement so that wooden floor with cement as directed. The flooring shall be a direct pressure laminate flooring (DPL) with AC-4 Grade material. The wooden flooring shall have wax sealed locking to block moisture seepage. The payment will be made as per actual measurements. At no point of time shall the premises be left open to natural elements. Cleaning of Office floor and providing polyethylene sheet above which a foam of 02mm(+/- 5%) shall be provided before installing the HDF Laminated Wooden flooring The rates shall be inclusive of all the taxes & GST, freight charges, fitting & fixing, disposal of waste and displacing and putting the office goods and workstation back to its original location in the office without any damage to the existing property/ structure, electrical fitting, network infrastructure etc.	9000	sq. ft.		
2	Beading	3000	Sq.Ft		
3	Skirting (60mm Height)	3000	Sq. Ft.		
4	Reducer Profile	500	Sq.Ft.		
	Mention the brand name of the Wooden flooring and its Code/Type no. and also submit its product brochures.				

	Rate in Words			
	GST (@)			
	TOTAL			
5	Less Buyback of old carpet Bajaj Carpet/PVC flooring (on As is basis) in the Office on all the floors and taking away from the site. The rates of the items shall be quoted by the agency.	L.S.		(-)
	Rate in Words	<u> </u>	1	
	Grand TOTAL			

Note:

- 1. The rates shall be inclusive of all taxes, freight charges, adhesive, wastage etc.
- 2. The payment will be made as per the actual measurement, including that of skirting.
- 3. The payment will be made after the entire work is finished in all the floors as mentioned above.
- 4. The quantities mentioned in the quotation are tentative and subject to variation. No escalation in the rates will be given to the agency. The time period for the completion of the work is 45 days.
- 5. The rates shall have the validity of 90 days from the date of opening of quotations.

Accepted terms and conditions

I/we have read and understood all instructions/ conditions and I have taken into account the terms and conditions of contract while quoting the rates.

(Sign of the Agency Rep)

Stamp of the Agency