



**National Bank for Agriculture and Rural Development (NABARD)  
Odisha Regional Office, Ankur 2/1, Nayapalli,  
Bhubaneswar, Odisha - 751015**

**Email- [dpsp.bhubaneswar@nabard.org](mailto:dpsp.bhubaneswar@nabard.org)**

**Ref No.NB.OD.RO.DPSP/ STAFF BOUNDARY WALL/2025-26**

**07/05/2025**

**QUOTATION- Repairs of Boundary Wall in NABARD Staff Quarters**

**GENERAL CONDITIONS & SCOPE OF WORK**

1. Maintain proper curing, cleaning for repairing work.
2. Maintain all safety factors at working site.
3. PCC, plastering, Brick work and cement concrete work should be done as per BOQ.
4. All the jobs given to the agency shall be taken up on priority basis without any delay by mobilizing all the resources immediately at site.
5. The Quoted rate shall be workable and inclusive of all material and labour cost as well as contractor profit, overheads/ income tax as applicable.
6. The final amount would be released on basis of actual measurement.
7. Maintain all safety factors for the residents as well as at working site.
8. The approved make shall be got approved from Engineer-in-charge/ NABARD Officials.
9. All debris along with waster material to be removed on timely basis and whenever advised by NABARD Representative.
10. The contractor must quote for all the items of BOQ in Price Bid. Bidders are also advised to visit the site of installation before bid submission.
11. Incomplete BOQ will not be considered.
12. No conditional bid/offer will be accepted.
13. The rates must be quoted by including GST even if the contractor is not registered with GSTN.
14. The quantities of material (mentioned in price bid) are indicative subjected to variation as per the requirement of execution.
15. In case of change in quantities pro rata payment will be made by NABARD.
16. The decision of the NABARD shall be final and binding on price bids and the tendering process.
17. **Estimated Cost of the Tender is Rs. 4.99 lakhs inclusive of all taxes.**
18. **The bidder should submit bids in sealed envelope at DPSP 3rd Floor, NABARD Odisha Regional Office, Ankur, Nayapalli, Bhubaneswar latest by 12 May,2025 14.00 hrs and the tender would be opened by 15:00 on the same day.**
19. Rate quoted includes all costs including profit, taxes etc.
20. Any change in quantity the pro-rata will be considered.
21. If there is discrepancy in the rates quoted in words and figures, then the rate indicated in words treated as final.
22. All terms and conditions are as per NABARD discretion.

23. Only approved specified quality and brand to be used by the contractor as in above BOQ.
24. Proper cleaning to be ensured after completion of the work.
25. The approved make shall be got approved from Engineer-in-charge/ NABARD Officials.
26. All kinds of cutting, Fixing, un-screwing, fabrication, etc as per site requirement.
27. Site visit is recommended before quoting of rates by the bidder.
28. All the bidders are advised in their own interest to be present on the specified date. No separate intimation will be given in this regard.
29. Bids would be opened even in the absence of any or all the vendors' representatives.

#### **PRICE BID**

<b>Sl No</b>	<b>Description.</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate. [Rs. Ps.]</b>	<b>Amount. [Rs. Ps.]</b>
1	Earth work in excavation in foundation trenches, column foundation, pit, etc in all kind of soil including moorum stony earth and earth mixed with boulders except sheet rock and boulders not requiring blasting including dressing of sides and levelling the bed up to the required depth and depositing the excavated materials away from the work site with initial lead of 50 mtr and all lifts, including shoring, shuttering & dewatering (if required) with cost of labour, labour cess, hire & running charges of all machineries, sundries & T&P required for the work complete as directed by the Engineer in charge.	68.62	Cum		
2	Supplying and filling with sand in foundation, well-watered and compacted, top surface dressed and levelled to proper level and gradient including cost of all materials, conveyance, royalties, loading, unloading, cost of all labour, T&P, etc. all complete as per the direction of Engineer-in-Charge.	9.89	Cum		

3	Providing, Supplying & laying in position machine mixed plain cement concrete in volumetric proportion (1:3:6) of any thickness (1 cement, 3 coarse sand, 6 Hard granite stone crusher broken aggregates of size 37 mm and down) in required thickness for foundation, laying, spreading, ramming, consolidating as per requirement and curing etc. including cost of all materials, transportation, loading, unloading, labour, T & P, taxes, duties, levies, octroi, royalties, etc. complete as per direction of Engineer -in-charge.	3.30	Cum		
4	Providing, supplying & laying in position machine mixed and machine vibrated reinforcement cement concrete of controlled M25 grade of specified volumetric proportion for cement concrete structural element in volumetric proportion (1:1:2) of any thickness (1 cement, 1 coarse sand, 2 Hard granite stone crusher broken aggregates of size 20 mm and down) in required thickness for foundation, columns, in any shape using 20 mm and down size of hard crusher broken granite aggregates, necessary lift & lead, finishing concrete surface including cost of all materials, cost of curing, transportation, loading, unloading, labour, T & P, taxes, duties, levies, octroi, royalties, etc. complete as per direction of Engineer -in-charge.	10.69	Cum		
5	Supplying & fixing steel reinforcement in superstructure for reinforcement concrete including transporting, decoiling, straightening, cutting, binding, placing in position at all level & binding with 18-20-gauge soft drawn annealed binding wire, welding if necessary complete as per specification & drawing etc complete as per Engineer -in-charge.	1004.4 3	Kg		
6	Providing, supplying and constructing brick masonry in cement mortar 1:6 (1cement :6 coarse sand) with fly-ash bricks having minimum crushing strength 70 kg/ sqcm at all levels with all necessary scaffolding ,racking out the joints, all materials, transportation, curing, loading, unloading, labour, T & P, taxes, duties, levies, octroi, royalties, etc complete as per direction of Engineer -in-charge.	17.95	Cum		

7	Providing, supplying & applying cement plaster in line & level at all height with cement mortar 1:5 (1 cement : 5 sand) to walls, beams, columns, ceiling, moulds, patta, grooves etc. including scaffolding, curing ,finishing smooth at all levels including cost of all materials, repair of all crack with mesh and proper coating, transportation, lift, loading, unloading, curing, labour, tools and plants, taxes, duties, levies, octroi, royalties, etc. complete as per direction of Engineer -in-charge.	201.30	Sqm t		
8	Providing and applying 1st quality approved exterior paint to all type of smooth plasters, concrete, ceilings etc surface. The surface to be painted shall be made free from any loose paint, dust, grease and any fungus, algae or moss, one coat wall primer be applied after which any surface imperfection such as holes, dents, fine cracks shall be corrected by filling with synthetic grade putty and then apply the premium emulsion in two coats. The colour and pattern/ colour combination of the paint shall be got approved from Engineer-in-charge/ NABARD Officials. The rate includes cost of all materials, labour, scaffolding, ladders charges, storing & safeguarding the labour in all heights. (Approved make:- Asian paint, Indigo, Dulux, Nerolac, Berger)	134.20	Sqm t		
9	Providing and fixing of M.S Grills of approved designs made out of M S Flat, Square bars/Round bars etc. of specifications / dimensions as directed by NABARD with necessary welded clamps fixed in proper position & plumb, making required holes in Masonry Walls / R.C.C Structures (where necessary) and grouting the clamps with C.C(1:2:4) with 12mm size black hard crusher broken granite stone chips, making good to the damages of Masonry Walls / R.C.C Structures including cost, conveyance, loading, unloading, stacking, royalties and taxes of all materials, cost of all labours, staging, scaffolding, sundries, T&P etc. complete as per the direction of the Engineer-in-	198.00	Kg		

	charge. The design and specification to be chosen by NABARD.				
10	<p>Providing and applying 1st quality synthetic enamel grade gloss/ stain paint. The surface to be painted shall be made free from any loose paint, dust, grease and any fungus, algae or moss, on it shall got be removed thoroughly by vigorous wire brushing and cleaning with water. Then one coat of exterior grade wall primer be applied after which any surface imperfection such as holes, dents, fine cracks and again surface imperfection to be corrected and again surface imperfection to be corrected. Thereafter again sand the surface with emery paper 320 and wipe clean and then apply the premium enamel in two coats. The colour and pattern/ colour combination of the paint shall be got approved from Engineer in charge. The rate includes cost of all materials, labour, scaffolding, ladders charges, storing &amp; safeguarding the labour in all heights. Contractor has to provide all safety precautions to all working labours at site.</p> <p>(Approved make-: Asian paint, Indigo, Dulux, Nerolac, Berger)</p>	26.40	Sqm		
11	<p>Providing, fitting and fixings concertina coil fencing with punched tape concertina coil 600mm dia 10 meter openable length having 50nos rounds per 6 meters length and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I staples and G.I clips to retain horizontal, including necessary bolts or G.I barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.)/Spring core (2.5mm thick) wire of high tensile strength. The rate includes cost of all materials, labour, scaffolding, ladders charges, storing &amp; safeguarding the labour in all heights. contractor must provide all precautions' and arrange safety belts, helmets to all working labours at site.</p>	24.00	Rmt		
12	<b>Total</b>			₹	
13	<b>All Total Including GST (18%)</b>			₹	

14	<b>All Total Including GST (18%) in words</b>	<b>Rupees</b>	
----	---	---------------	--

Accepted all terms & conditions of the tender.

Place :

Date :

Address :

(Signature of the Tenderer)

Name and Seal