

BOQ for Installation of Aluminium Windows in 22 flats of NABARD Residential Complex Channi Rama, Jammu (J&K)

S.No	Description	Qty.	Unit	Rate per unit (Rs.)	Amt. (Rs.)
1	Dismantling of existing M.S. windows, stacking of useful material, disposal of unserviceable material, as directed by ACT of NABARD/Supervising official of work, plastering/painting of broken area and fixing tile on the base of window	22	Job		
2	Providing and fixing aluminium windows (including frame, tubes, sections, shutter and handles) with float glass panes of 4.0 mm thickness and Providing and fixing fly proof S.S. wire gauze to windows and clestory windows using S.S. wire gauge (grade 304)with average width of aperture 1.4 mm in both directions with wire of dia 0.50 mm all complete of approved make with provision for Windows AC, conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, complete in all aspects: a) For fixed portion:14 Guage. Powder coated aluminium (minium thickness of powder coating 50 micron). b) For shutters of windows 14 Guage including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required. Powder coated aluminium (minium thickness of powder coating 50 micron). (Block No.2 - Flat Nos.1, 2, 3, 4, 5, 6; Block No.3 - Flat Nos.2, 5, 6, 8; Block No.4 - Flat Nos.1, 2, 3, 4, 5, 6, 7, 8; Block No.6 - Flat Nos.6, 7; Block No.7- Flat Nos. 3, 4)	260	Sq mtr.		
Total Amount (1+2)					