

NB (Kerala)/ DPSP/ 74009/OM-12/ 2025-26  
25 September 2025

### Corrigendum

**Renovation of Men and Ladies Toilets of 1<sup>st</sup> and 7<sup>th</sup> floors of NABARD Kerala Regional Office, Punnen Road, Statue, Thiruvanthapuram, 695001 ( Only for the empaneled vendors)**

With reference to our tender NB (Kerala)/DPSP/81725/OM-12/2025-26 dated 01 September 2025, please note that the technical specification for BOQ item number 5 was inadvertently stated in the Bill of Quantities. The corrected item along with its technical description is provided below:

BOQ item number	Existing item particular	Existing item quantity	Revised item particular	Revised item quantity
5	Buy-back of old 6mtr GI poles (This includes removal of foot concrete also)-	25 Numbers	Acoustic Ceiling Tiles – Installation (Suspended Grid System) Materials • Acoustic ceiling tiles (2x2 or 2x4) • T-grid system (main runners, cross tees, wall angles) • Suspension wires or rods with hooks/anchors • Drill, screws, pliers, measuring tape, level, utility knife Steps: 1. Mark Ceiling Level • Decide ceiling drop height. • Snap a level line around the walls where wall angles will be fixed. 2. Fix Wall Angles • Screw wall angles (L-shape channels) along the marked line around the room perimeter.	570 Square feet.

राष्ट्रीय कृषि और ग्रामीण विकास बैंक

1 | Page

**National Bank for Agriculture and Rural Development**

केरल क्षेत्रीय कार्यालय

राष्ट्रीय कृषि और ग्रामीण विकास बैंक केरल क्षेत्रीय कार्यालय, पुन्नेन रोड, स्टाचु, तिरुवनंतपुरम - 695001 टेलि: 0471 2701600/700 ई-मेल: trivandrum@nabard.org

Kerala Regional Office


National Bank for Agriculture and Rural Development, Kerala Regional Office, Punnen Road, Statue Thiruvananthapuram – 695001

Tel :- 0471 2701600/2701700 • E-mail: trivandrum@nabard.org

			<p>3. Install Suspension Wires</p> <ul style="list-style-type: none"><li>• Drill holes in the slab above, fix anchors, and hang suspension wires at ~4 ft (1200 mm) spacing.</li><li>• Ensure all wires hang at the same height.</li></ul> <p>4. Fit Main Runners</p> <ul style="list-style-type: none"><li>• Suspend the main T-runners (usually 12 ft long) from the wires.</li></ul>	
--	--	--	---	--

The revised Bill of Quantities (BOQ) is enclosed. Vendors are requested to quote their rates based on the revised BOQ. All other terms and conditions of the tender remain unchanged.

Yours Faithfully



**(Sajeev S)**  
**Deputy General Manager**