



ರಾಷ್ಟ್ರೀಯ ಕೃಷಿ ಮತ್ತು
ಗ್ರಾಮೀಣ ಅಭಿವೃದ್ಧಿ ಬ್ಯಾಂಕ್
ಕರ್ನಾಟಕ ಪ್ರಾದೇಶಿಕ ಕಛೇರಿ
ನಬಾರ್ಡ್ ಟವರ್, # 46, ಕೆಂಪೇಗೌಡ ರಸ್ತೆ,
ಬೆಂಗಳೂರು - 560 009
ದೂ : +91 80 22076400
ಫ್ಯಾಕ್ಸ್ : +91 80 22222148
ಇ-ಮೈಲ್ : bangalore@nabard.org
ವೆಬ್‌ಸೈಟ್ : www.nabard.org

राष्ट्रीय कृषि और ग्रामीण विकास बैंक
कर्नाटक क्षेत्रीय कार्यालय
नाबार्ड टावर,
46, केंपेगौडा रोड,
बेंगलूर - 560 009.
टेली: +91 80 22076400
फैक्स : +91 80 22222148
इमेल: bangalore@nabard.org
वेबसाईट: www.nabard.org

National Bank for Agriculture
and Rural Development
Karnataka Regional Office
NABARD TOWER,
46, Kempe Gowda Road,
Bangalore - 560 009.
Tel: +91 80 22076400
Fax : +91 80 22222148
E-mail: bangalore@nabard.org
Website: www.nabard.org

No. NB/DPSP / /Flat Renovation/ Executive VOF B-104 /2017-18
TENDER CORRIGENDUM

28 August 2017

M/s.

Dear Sir/ Madam,

**CORRIGENDUM- TENDER FOR RENOVATION (CIVIL, ELECTRICAL, PLUMBING AND INTERIOR WORKS)
OF EXECUTIVE VOF FLAT No. B-104 AT NABARD QUARTERS, RAHEJA PARK APARTMENT, MAGADI
ROAD, BANGALORE- 560079**

Please refer to our Notice Inviting Tender (NIT) no. NB/ DPSP/ / Flat Renovation/ Executive VOF B-104/ 2017-18 dated 22 August 2017 on the captioned subject. In this connection, we advise that the Nabard Regional Office Karnataka has decided to bring in certain changes in the proposed work, mentioned as follows:

1. In the remodeling of the Executive VOF Flat B-104 at Raheja Park, the existing partition wall between the living room and existing Bedroom 1 need not be dismantled. Accordingly, the revised drawings are uploaded in the tenders section in our website www.nabard.org under the captioned heading. All the bidders are requested to download the same for the process of submission of tenders.
2. The actual quantity of work may vary from the quantity indicated in the Schedule of works during execution depending upon the Bank's requirement.
3. The revised Schedule of Quantities provided in the Price bid due to the modification can be read as follows:

Reference Sl. No. in Item of Works	Item of Work (REVISED DESCRIPTION OF WORK)	Qty.	Unit	Rate	Amount (in Rs.)
Item No. 3 Pg. 22 (Interior Works)	New Full Wardrobes in Bedroom of Openable type door: Providing and fabricating 7' height and 2' deep floor storage cabinet as per the design by using 19mm BWP/BWR block board/ Plywood of century/kitply/greenply/national make. The cabinet fabricated all round block board of 0.45/0.40 mt widths to form a box at rear side shall be fixed with 9mm	30.00	SFT		

	<p>thick ply. Front shall be fixed with two half shutters according to the size of cabinet. The cabinet will also have equal partition shelves inside. Inside and front lipping shall be done by 6m ply to form the grove. All cut edges of the block board shall be fixed with beech wood beading shall be polished finished with color less polish finished neatly. All exterior surface of the block board shall be fixed with 4mm thick VENEER with PU coat and required fevicol finished neatly, all interior surface of the block board shall be finished with 0.8mm thick approved colour laminate. Lastly the cabinet will get fitted with H/D type SS handles of size 15cm, multi lock, hinge/ channels, laminated Etc complete. This rate includes cost of all materials, labor, and taxes, lead and lift, to the place of work.</p>				
<p>Item No. 4 Pg. 23 (Interior Works)</p>	<p>Wardrobe Cabinets above loft in Bedrooms / passage loft : Providing and fabricating 2'6" and 2' deep floor storage cabinet above 7'0" level as per the design by using 19mm BWP/BWR block board/ Ply of approved make. The cabinet fabricated all round block board of 0.45/0.40 mt widths to form a box at rear side shall be fixed with 9mm thick ply. Front shall be fixed with two half sliding / openable shutters according to the size of cabinet. The cabinet will also have equal partition shelves inside. Inside and front lipping shall be done by 6m ply to form the grove. All cut edges of the block board shall be fixed with beach wood beading shall be polished finished with color less polish finished neatly. All exterior surface of the block board shall be fixed with 4mm thick VENEER and PU coat with required fevicol finished neatly,</p>	8.00	SFT		


	all interior surface of the block board shall be finished with 0.8mm thick approved colour laminate only as per instructions of architect.				
--	--	--	--	--	--

Sq. M : Square Metre; Cu. M: Cubic Metre; RMT: Running Metre; Kgs.: Kilogram; SFT: Square Feet

ALL OTHER ITEM OF WORKS IN THE SCHEDULE OF QUANTITIES AS MENTIONED IN THE PRICE BID WILL REMAIN SAME AND HOLD GOOD.

4. The bidder should quote the rates and amount (in Rs.) inclusive of the above item of works.
5. In addition, if any item of works needs to be added, as found required during execution, such item of work may be added and the rate will be worked out as mentioned in the terms and conditions of the tender document.
6. This may please be treated as part of original tender document. All other terms and conditions will remain same as the original tender document.

Yours faithfully



A R Shivaramakrishnan
(Asst. General Manager)