

**Item Rate BoQ**

**Tender Inviting Authority:** Chief General Manager, Department of Premises, Security and Procurement, NABARD, Head Office, Mumbai

**Name of Work:** Tender for Design, Supply, Installation, Testing, Commissioning and Maintenance of 02 Nos. Passenger Lifts at NABARD House, G Block BKC, Bandra Kurla Complex, Bandra East, Mumbai, Maharashtra 400051

**Contract No: NB.HO./DPSP/Lift Installation at NABARD HOUSE/ 93217 /2025-26**

Name of the Bidder/ Bidding Firm / Company :										
<b>PRICE SCHEDULE</b> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)										
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (without GST) Rs. P	Total Amount without Taxes Rs. P	GST (%)	GST Amount Rs. P	TOTAL AMOUNT With Taxes Rs. P	TOTAL AMOUNT In Words	
1	2	4	5	13	49	50	51	53	55	
1	Design, Supply, Installation, Testing Commissioning and Maintenance of 8 passenger Capacity lift serving 11 stops @ 1.50 MPS as per data sheet along with detailed specifications and the scope of work in Part I.	2.00	Nos		0.00	18.00	0.00	0.00	INR Zero Only	
2.1	Civil Work: Elevator related civil work such as minor repairs to lift shaft internally with patch work and re-plaster wherever required, buffer blocks, sill grouting, front wall modifications on all floors including gap filling, plastering on both sides to suit automatic doors, machine mounting blocks in machine room, white washing with 2 coats in lift shaft and machine room, Buttons and indicator box grouting on all floors, FMS and alarm box on ground floor, minor chipping work wherever the lift shaft is not in plumb, Core cutting of holes in existing slab to suit new machine. Repairs to existing machine room if any, providing smoke vent with jail and louvers etc.	2.00	Nos		0.00	18.00	0.00	0.00	INR Zero Only	
2.2	Electrical Work including changing of 3-phase armoured power cables, Iron clad Mains Switches for 3 phase and single phase car light and machine room and shaft lights, MCB, ELCB, RCCB, 1-phase armoured cable, bulkhead fittings with LED on each floor, earthing pit, and double earthing in copper, machine room lighting wiring. Exhaust fans in machine room with grillwork	2.00	Nos		0.00	18.00	0.00	0.00	INR Zero Only	
3	Rebate for buying back and taking away for all dismantled equipment of existing old lift as indicated in data sheet	2.00	Nos		0.00	18.00	0.00	0.00	INR Zero Only	
4	Comprehensive annual maintenance charges inclusive of all taxes, transport, insurance, handling etc. as applicable after guarantee period as per terms & conditions specifies in Part I on per year for proposed new lifts only for the 1st year.	2.00	Nos		0.00	18.00	0.00	0.00	INR Zero Only	
5	CAMC charges for 19 years (arrived after multiplying with Multiplication Factor as per Cl. 4.2 under Sec-II of Tender Document)	2.00	Nos	0.00	0.00	18.00	0.00	0.00		
Total in Figures									0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only								