

**FINANCIAL BID**  
**FOR PROPOSED REPAIR, RENOVATION AND PAINTING OF BOUNDARY WALL OF**  
**NABARD RESIDENTIAL COMPLEX, NABARD GRAM, CHANNI RAMA, JAMMU**

<b>Sr. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>UNIT</b>	<b>Rate (INR)</b>	<b>Amount (INR)</b>
1.	Dismantling Concertina Coil in fencing including making rolls and stacking within 50 m lead.	285.00	RMT		
2.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.  Front Side Wall Left Side Back Side Right Side	620.00	M2		
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete,including disposal of rubbish to the dumping ground within 50 metres lead and repairs to foundation: With cement mortar 1:4 (1Cement: 4 Coarse Sand) Front Side Wall Left Side Back Side Right Side	1111.00	M2		
4.	<b>Removing white or colour wash by scrapping and sand papering and preparing the surface smooth with putty as per the site conditions including necessary repairs to scratches etc. complete</b>  Front Side Wall & Security Room Left Side Back Side Right Side	1912.00	M2		
5.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) Boundary Wall Left Side & Front Side	19.85	CUM		

	Pillar				
6.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) For Coping over Pillars	3.6	CUM		
7.	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform For Coping	18.00	M2		
8.	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand) Over Repair Work Over Pillars	196.50	M2		
9.	Applying priming coats with primer of Nerolac/Asian or Equivalent brand as per approval and manufacturer having low VOC (Volatile Organic Compound) content. With water thinable cement primer on wall surface having VOC content less than 50 grams/ltr	2200.00	M2		
10.	Finishing walls with Acrylic Smooth exterior paint of Nerolac/Asian or Equivalent Brand of required shade : New Work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	2200.00	M2		
11.	Providing and Fixing of two feet high MS Grill on existing grill to be welded as per direction and drawings provided by architect on boundary wall including One coat of Primer and Two or More coat of Enamael Paint of approved shade and make. The Grill shall be fixed to the boundary wall including MS Flat 50x50x6 (2 nos) as per the detailed drawing and complete in all respect. Front and Left Side	129.00	M2		
12.	Taking out of Existing Y shaped MS angle over Boundary Wall Columns and embeded and grouting the same in pre hollow pockets 150x150x150 mm in the new Columns including One coat of Primer and Two or More coat of Enamael Paint of approved shade and make. The Y	100.00	Nos.		

	shaped angle shall be fixed to the boundary wall as per the detailed drawing and complete in all respect. Over Boundary Wall Columns				
13.	Applying priming coats with primer of Nerolac/Asian or Equivalent brand as per approval and manufacturer having low VOC (Volatile Organic Compound ) content and finishing existing MS Grill with enamel paint of Nerolac/Asian or Equivalent Brand of required shade.	150	M2		
<b>Total</b>					
<b>Total in Words:</b>					

**Note: Conditional tenders will be rejected summarily.**

PLACE:

DATE:

(SIGNATURE OF THE TENDERER)

ADDRESS:

NAME AND SEAL: